

INVITATION TO QUOTE

Opportunity ID: ITQ25-03

Opportunity Title: Goodwin Park Paved Walking Path

Official Contact: Doug Lowther, dlowther@fortstjames.ca

Requirements and Specifications

The District of Fort St. James is seeking Quotes to construct and install a paved walking path around the perimeter of Goodwin Park, of an estimated length of .6km (600mtrs) The contractor will be responsible for the excavation, construction and compaction of base, all preparation and paving.

All Quotes must include mob and de-mob, LOA, and hauling or transporting equipment, materials or supplies. This can be broken out separately in pricing. Conceptual drawing attached for reference only, to type of design and concept of the walking trail within the perimeter of the park, measurements are not exact, and only for conceptual design reference. District representatives will meet with Contractor who is successful in the quotation process, to walk the area, and District representative will /paint mark the pathway parameters.

Project Scope:

- Removal and Disposal: Removal and disposal of soil and existing materials to a depth of 150mm over the entire path area,
- Base Installation: Laying and compaction of a 100mm thick crushed base material,
- Path Length: Approximately 600 metres,
- Path Width: 1.5 metres, as per the concept drawing, and
- Paving: Asphalt paving to a thickness of 50mm.

Site Preparation and Cleanup:

- All hauling, removal of excess or old materials must be included within the proposal and priced.
- All signage, barriers, preparation work, and necessary equipment are to be supplied by the contractor

Operational Requirements:

- All works can be carried out on the weekdays between the 7:00AM and 7:00PM,
- All works can be carried out on the weekends between 9:00AM and 5:00PM, and
- Water is available for contractors water trucks at no charge.

